



June 14, 2021

TO: ALL PLANHOLDERS OF CITY OF DALLAS

**DALLAS WATER UTILITIES FIVE-MILE CREEK WASTEWATER PIPE REPLACEMENT
– GLENDALE PARK PROJECT
CONTRACT NO. 21-124**

Attached is Addendum No. 2 to the subject contract. Please incorporate into your bidding documents.

Rishi Bhattarai

Rishi Bhattarai, P.E.
Senior Program Manager
Pipeline Project Management

Water Utilities Department

Capital Improvements • 2121 Main Street, Suite 300 • Dallas, Texas 75201 • 214-948-4560 • Fax 214-243-1118
A City Utility Providing Regional Water and Wastewater Services Vital to Public Health and Safety

**ADDENDUM NO. 2
FOR
CONTRACT NO. 21-124
DALLAS WATER UTILITIES FIVE-MILE CREEK WASTEWATER PIPE REPLACEMENT
– GLENDALDE PARK PROJECT**

NOTICE TO ALL BIDDERS

June 14, 2021

A4. BID ITEMS

DELETE THE FOLLOWING ITEMS:

- 1. Bid Item 3560 CONNECTION TO EXISTING MANHOLE**
- 2. Bid Item 6160AE 48" SPECIAL MANHOLE**

ADD THE FOLLOWING BID ITEMS:

ITEM NO. 3560A CONNECTION TO EXISTING LARGE DIAMETER PIPE

This item consists of furnishing and placing approximately **4** Each Connection to dissimilar large diameter pipes, in accordance with **Item 507.COD Open-Cut – Wastewater Conduit Installation** of these specifications and addenda thereto, and the applicable Standard Drawings and Details.

Measurement and payment will be per each in place in accordance with **Item 507.6. Measurement. Measurement and Payment For Wastewater Conduit Installation** of these specifications.

ITEM NO. 6120AE 48" DIAMETER PRESSURE TYPE MANHOLE

This item consists of furnishing, placing, and protecting from corrosion by Epoxy Coating or other approved method approximately **2** Each **48"** Diameter Pressure Type Manhole in accordance with **Item 502.1. Manholes, Item 502.1.2.COD: Wastewater Manhole Adjustments, Item 502.1.4.8.COD: Wastewater Manhole Frame Seals, Item 502.1.4.9.COD: Interior Coatings For Manholes, and Item 502.1.7.COD: Manhole Backfill** of these specifications and addenda thereto, and the applicable Standard Drawings.

Removal of any existing conflicting manhole, if required, will be included in this item. Non-shrink grout shall be used in place of mortar. This item shall include barricading.

Measurement and payment will be in accordance with **Item 502.1.6.COD: Measurement and Payment of Manholes** of these specifications.

ITEM NO. 7061A CLASS 'B' CONCRETE ANTI-FLOTATION SLAB

This item consists of furnishing and placing approximately **185** Cubic Yards of Class 'B' Concrete Backfill in accordance with **Item 504.6.3. Concrete Backfill, Item 504.3.2. Foundation, Item 502.4.1. Concrete Blocking, Item 702.2. Mix Design and Mixing Concrete For Structures, and Item 107.27.COD: Environmental Compliance** of these specifications and addenda thereto, and the detail drawings on the plan sheets.

Concrete anti-flotation slab will be placed above the crown of the pipe as indicated on the plan sheets. The provisions of **Item 104.2.1. Increased Or Decreased Quantities of Work** of the specifications regarding negotiating for revised consideration for over/underruns do not apply to this item.

Measurement and payment shall be made at the contract unit price per cubic yard of concrete, calculated per the dimensions noted on the plan sheets along the pipeline length. This shall include furnishing and placing all materials and all labor, tools, equipment and incidentals necessary to complete the work, all in accordance with the plans and specifications. No allowance for waste shall be made.

ITEM NO. 7560 CRUSHED ROCK FOR TEMPORARY PAVING BASE

This item consists of furnishing and placing approximately **385** Cubic Yards of Crushed Rock (Flexible Base) for Temporary Paving Base material in accordance with **Item 402.4.COD: Replacing Paved Surfaces and Item 301.5. Flexible Subbase Or Base (Crushed Stone/Concrete)** of these specifications and addenda thereto.

Measurement and payment will be in accordance with **Item 402.4.10. Payment For Pavement Replacement** of these specifications.

REVISE THE FOLLOWING BID ITEM QUANTITY:

Increase quantity for Bid Item 7801J - 8" Reinforced Concrete Pavement or Base from **945 Square Feet to 38,275 Square Feet.**

SPECIAL SPECIFICATIONS (Attachment No. 1)

Part T – Technical Specifications: Replace entire Special Specifications section prepared by Freese & Nichols, Inc. in its entirety and replace with Addendum No. 2 version of Special Specifications provided.

CONTRACT DRAWINGS (Attachment No. 2)

Replace entire Drawing Set prepared by Freese & Nichols, Inc. in its entirety and replace with Addendum No. 2 version of Drawing Set provided.

BID PROPOSAL SPREADSHEET (Attachment No. 3)

Replace bid proposal spreadsheet with revised Addendum No. 2 Bid Proposal Spreadsheet,

PRE-BID MEETING ATTENDANCE SHEET (Attachment No. 4)

The Pre-Bid Attendance Sheet is provided as Attachment No. 4.

